BRUHAT BANGALORE MAHANAGARA PALIKE
DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division

SCHDULE-B

Name of Work: Improvements of RCC drain & Covering slab Dasarahalli Metro station to Bylappa Circle Right side road in Dasarahalli Ward No 15

Sl	Description of Work	Unit	Qty	Sanctioned Rates	
				In figures (Rs)	In Words (Rs)
1	2	3	4	5	6
1	Dismtling of existing structures like culverts, Bridges, retaining walls and other structure comprising of masonary, cement concrete, wood work,steel work, including T&P and scaffolding whereever necessary, sorting the dismanlet material, disposal of unserviceable material and stacking the serviceable material with all lifts complete as per specification Lime/Cement concrete I. By Manual Means C. Prestressed /Reinforced cement concrete Grade M-20 & above	Cum	265.44	1684.34	Rupees One Thousand Six hundred eighty four & thirty four Paise Only
2	Earthwork excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.	Cum	911.82	189.74	Rupees One Hundred Eighty Nine & Seventy four Paise Only
	Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications.	Cum	115.29	5421.90	Rupees Five Thousand Four hundred twenty one & Ninety Paise Only

EXECUTIVE ENGINEER-4
KRIDL, DRMP DIVISION

EXECUTIVE ENGINEER
Bruhat Bangalore Mahanagara

Scanned by CamScanner

4	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. with 20mm and down size granite metal coarse aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compacted for walls and bottom including centering, shuttering, cost of materials, HOM of machinery, curing etc., complete excluding cost of steel as per MORTH specification	Cum	306.36	7070.20	Rupees Seven Thousand Seventy & Twenty Paise Only
5	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	497.70	2208.00	Rupees Two thousand two hundred eight Only
6	Supplying, fitting and placing TMT bar Fe 500 reinforcement in sub-structure complete as per drawing and Technical Specifications complete as per specificationsMORTH Specification No.1600 & 2200	Tonne	19.80	72326.98	Rupees Seventy two Thousand Three hundred twenty six & Ninety eight Paise only
7	Providing and laying Pre cast drain cover slab of 250mm thickness including cost of all Materials Labour, curing, Transportation, Loading & un loading etc. as per direction of the Engineer Incharge	Sqm	78.75	5241.00	Rupees Five thousand Two hundred Forty One Only
	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) [illegible]te for haulage of materials as per item [illegible]4/KSRRB : M100-4.1 ..... Rs. 2.00 [illegible]m b) Average earth of work 1.28 [illegible]m for Rs. 2.00/Km c) Add loading and unloading	Cum	1177.26	69.80	Rupees Sixty Nine & Eighty paise only

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

Executive Engineer
Dasarahalli Division

Scanned by CamScanner